



DETAIL TYPE C

TYPICAL BELOW GROUND WALL/ FLOOR DETAIL

NB : DO NOT SCALE - USE FIGURED DIMENSIONS ONLY.

Project: Standard Detail : Visqueen Cavity Drain Membrane System.			
NB-CD-01	Ground Bearing Raft	Cavity Drain	N/A
Visqueen Building Products Contact Technical Support : t : 0333 202 6800 f : 0333 202 6886 e : enquiries@visqueenbuilding.co.uk www.visqueenbuilding.co.uk			
COPYRIGHT RESERVED.			
New Build Cavity Drain			

- Detail Issued For Guidance Only, Designer's Approval Required
- Site construction sequencing should be assessed before the appropriate Visqueen Standard Detail is selected & approved by the Designer
- All cut-outs in concrete slabs to Structural Engineer's design
- Visqueen Water Channel to be surrounded in 20mm rounded washed stone

WATCH POINTS :-

- 1) Ensure V20 Floor Membrane "domes" are filled as necessary to transmit floor loading.
- 2) Use mortar infill at the edge of the V20 Floor Membrane to provide a flush surface for bonding the CD 150mm Corner Strip.