



Detail Issued For Guidance Only,  
Designer's Approval Required

This construction sequencing should be assessed before the appropriate Visqueen Standard Detail is selected & approved by the Designer

All cut-outs in concrete slabs to Structural Engineer's design

Visqueen Water Channel to be surrounded in 20mm rounded washed stone

## DETAIL TYPE A & C

## TYPICAL BELOW GROUND WALL/ FLOOR DETAIL

NB: DO NOT SCALE - USE FIGURED DIMENSIONS ONLY.

		Visqueen Building Products Contact Technical Support : T: 0333 202 6800 F: 0333 202 6886 E: <a href="mailto:enquiries@visqueenbuilding.co.uk">enquiries@visqueenbuilding.co.uk</a> <a href="http://www.visqueenbuilding.co.uk">www.visqueenbuilding.co.uk</a>	
Project: Standard Detail : Visqueen Cavity Drain Membrane System.			
NB-CD-02	Ground Bearing Raft	Cavity Drain	N/A
New Build Cavity Drain			

- WATCH POINTS :-**
- 1) Ensure V20 Floor Membrane "domes" are filled as necessary to transmit floor loading.
  - 2) Use mortar infill at the edge of the V20 Floor Membrane to provide a flush surface for bonding the CD 150mm Corner Strip.