



Detail Issued For Guidance Only,
Designer's Approval Required

Site construction sequencing should be assessed before the appropriate Visqueen Standard Detail is selected & approved by the Designer

All cut-outs in concrete slabs to Structural Engineer's design

Visqueen Water Channel to be surrounded in 20mm rounded washed stone

TYPICAL BELOW GROUND WALL/ FLOOR DETAIL : NEW CONCRETE

DETAIL TYPE B & C

NB: DO NOT SCALE - USE FIGURED DIMENSIONS ONLY.

		CAVITY DRAIN MEMBRANE SYSTEM		Visqueen Building Products Contact Technical Support : T : 0333 202 6800 F : 0333 202 6886 E : enquiries@visqueenbuilding.co.uk www.visqueenbuilding.co.uk	
Project: Standard Detail : Visqueen Cavity Drain Membrane System.				© Visqueen 2018/19/20	
NB-CD-03	Ground Bearing Raft	Cavity Drain	N/A	New Build Cavity Drain	

- WATCH POINTS :-**
- 1) Ensure V20 Floor Membrane "domes" are filled as necessary to transmit floor loading.
 - 2) Use mortar infill at the edge of the V20 Floor Membrane to provide a flush surface for bonding the CD 150mm Corner Strip.