



Detail Issued For Guidance Only,
Designer's Approval Required

This construction sequencing should be assessed before the appropriate Visqueen Standard Detail is selected & approved by the Designer

All cut-outs in concrete slabs to Structural Engineer's design

Visqueen Water Channel to be surrounded in 20mm rounded washed stone

TYPICAL BELOW GROUND WALL/ FLOOR DETAIL : NEW CONCRETE (OPC)

DETAIL TYPE A B & C

NB: DO NOT SCALE - USE FIGURED DIMENSIONS ONLY.

		Visqueen Building Products Contact Technical Support : • 0333 202 6800 • 0333 202 6886 • enquiries@visqueenbuilding.co.uk www.visqueenbuilding.co.uk	
Project: Standard Detail : Visqueen Cavity Drain Membrane System.		© Visqueen 2014	
NB-CD-05	Ground Bearing Raft	Cavity Drain	N/A
New Build Cavity Drain			

- WATCH POINTS :-**
- 1) Ensure V20 Floor Membrane "domes" are filled as necessary to transmit floor loading.
 - 2) Use mortar infill at the edge of the V20 Floor Membrane to provide a flush surface for bonding the CD 150mm Corner Strip.