



Detail Issued For Guidance Only,  
Designer's Approval Required

This construction assembly should be assessed before the appropriate Visqueen Standard Detail is selected & approved by the Designer

All cut-outs in concrete slabs to Structural Engineer's design

Visqueen Water Channel to be surrounded in 20mm rounded washed stone

## DETAIL TYPE B & C

## TYPICAL BELOW GROUND WALL/ FLOOR DETAIL : NEW CONCRETE

NR : DO NOT SCALE - USE FIGURED DIMENSIONS ONLY.

		Visqueen Building Products Contact Technical Support : • (0333) 202 6800 f (0333) 202 6886 • <a href="mailto:enquiries@visqueenbuilding.co.uk">enquiries@visqueenbuilding.co.uk</a> www.visqueenbuilding.co.uk	
Project: Standard Detail : Visqueen Cavity Drain Membrane System.			
NB-CD-04	Ground Bearing Raft	Cavity Drain	N/A
New Build Cavity Drain			

### WATCH POINTS :-

- 1) Ensure V20 Floor Membrane "domes" are filled as necessary to transmit floor loading.
- 2) Use mortar infill at the edge of the V20 Floor Membrane to provide a flush surface for bonding the CD 150mm Corner Strip.